



NOTES

1. TIE-IN VALVE SHALL BE OPERATED BY IRCDUS PERSONNEL ONLY AND IN THE PRESENCE OF THE ENGINEER OF RECORD.
2. ALL LINES TO BE FULL PIPE FLUSHED.
3. ALL MATERIALS TO BE PER IRCDUS APPROVED MANUFACTURERS' PRODUCT LIST.
4. A 2" TEMPORARY JUMPER TO BE USED UNLESS OTHERWISE DIRECTED BY IRCDUS.

INDIAN RIVER COUNTY
 DEPARTMENT OF
 UTILITIES SERVICES



TEMPORARY
 JUMPER DETAIL

DRAWING
 NO.

W-12

SEPTEMBER 2011